

**HERMOSA WATER DISTRICT
PROGRAM, PLAN AND PROJECTS
FY 2020**

PROJECTS	SCOPE OF WORK	BENEFICIARIES	COST OF PROJECT	STATUS
Installation of VFD @ Mabuco PS	Supply & installation of variable frequency drive	HWD Concessionaires	485,000.00	100% Completed
Emergency Rehabilitation of Mabuco Pumping Station Deep Well	Pull-out of existing pump, removal of sediments, perforation of pipe casing, installation of gravel pack, treemie pipe, well casing, clay seal & cement grout. Including well development and pumping test.	HWD Concessionaires	660,234.00	100% Completed
Supply of Labor & Equipment for the Rehabilitation of Pipeline @ Purok 6, Brgy. Palihan	Trench excavation, pipelaying & installation of fittings, demolition & restoration of concrete pavements.	HWD Concessionaires	240,778.00	100% Completed
Supply of Materials, Labor & Equipment for the Construction of 40 Cu. M. Elevated Steel Water Tank @ Roman Highway PS	Excavation, reinforced concrete foundation works, backfilling & assembly/erection of elevated steel water tank.	HWD Concessionaires	938,440.00	100% Completed

PREPARED BY:

KAY FEEBALING

Project, Planning, and Development Officer B - City Division Manager C

RECOMMENDING APPROVAL:

MOISES SANTOS

City Division Manager C

APPROVED BY:

ENGR. GIDEON S DE LEON

General Manager